

## Rear Window Trench Hood user's manual

It is compatible with both right-hand drive and left-hand drive models/ 4-door and 2-door hardtop models

Please check to make sure that all parts shown below are present Rear Window Trench Hood (Product) 1 piece (Ton) Rear glass side (Bottom) Body side **▲**mark Check that a double-sided tape is attached to the top and bottom of the rear side of the product. \* The  $\blacktriangle$  marks on the left and right indicate where to install the Wrangler (JK).

### Compatible car models

Jeep Wrangler (JL): 2017-Up

It is compatible with four-door and two-door hardtop models,

This cannot be installed on soft-top vehicles

Jeep Wrangler (JK): 2011-Up

It is compatible with four-door and two-door hardtop models. \*Cannot be installed on vehicles prior to the first half of 2011 year model,

(Rear glass is too small, so it will stick out.) \*This cannot be installed on soft-top vehicles

This product is compatible with vehicles as of July 2023, the survey date.

Thank you for your purchase.

Please read this user's manual in its entirety before using the product.

Specialized skills and knowledge are required to properly install this product. If you are not confident that you can complete installation

> on your own, we recommend hiring a specialist. \* Note to hired installation specialists Make sure to return this user's manual

to the owner after installation. This user's manual contains important warnings and user notices. Please keep it in an easily accessible location inside the vehicle to facilitate reference at any time

- •Do not install this product anywhere other than the prescribed location, \* SEIKOSANGYO CO., LTD. is not responsible for any accident, breakdown malfunction or loss resultingfrom incorrect installation, disassembly or alteration of the product causedby failure to follow the warnings and user notices in this manual.
- Adhere the product in position on a warm day.
- •Be aware that the adhesive strength immediately after adhering the product is not very strong
- \* The adhesive strength of the double-sided tape is at its strongest 24 hours after adhering the product.
- This product uses strong double-sided tape and cannot be removed. If the product is removed, the surface on which it was attached may be damaged.
- Seikosangvo Co., Ltd. takes no responsibility, and will pay no damages/ compensation, for any change or irregularity in the user's vehicle resulting from product installation or usage, including malfunction, breakage, scratches, discoloration, marks or similar.
- ●While materials with outstanding heat-resistant and weather-resistant properties are used in this product, the product may deform or deteriorate due to conditions inside the vehicle in extreme heat or due to aging and



Based on woven nylon originally developed for use in military body armor, CORDURA\* Ballistic Fabric is dense and rugged, utilizing high-tenacity nylon 6,6 filament yarns that offer enhanced tear and abrasion resistance.

azuto.co.jp/en/ 548MHG042009A

### Contact Information for Product-related Inquiries

Customer Service Center E-mail: azuto-mk@seikosangyo.co.jp

- \* Jeen is a registered trademark of Stellantis N.V.
- \* CORDURA® and the CORDURA® logo are trademarks of INVISTA. \* AZUTO is a registered trademark of SEIKOSANGYO CO., LTD. \* Planning Design and Quality control for this product were carried out in Japan.
- \* Product specifications and appearance are subject to change without prior notice.


  \* All other product names, etc. used in this document are the trademark or registered trademark of their respective owners.
- SEIKOSANGYO CO., LTD. Main material

Saitama , 342-0043, Japan

SS- Made in JAPAN

# Installation position and method






(1) Pull the weather strip at the top of the rear window towards you to remove it until the left and right corner joints are visible.











(2) Pass the product through the heater cable so that the CORDURA® name tag on the side with the stitching (upper side) of the product ends up on the upper right.

Make sure to avoid forcibly pulling the product while working. Insert the lower side of the product into the groove as shown in Figure 2.





(3) Align the Wrangler (JL) and (JK) with the joint positions on the left and right, respectively, before installing this product. Attach the product to align along the edge on the upper side where the weather strip has been removed while peeling off the (white) release paper. (Figure 2)





(4) After attaching the product, reinsert the weather strip removed in step (1) in its original position, (Figure 3)


Push in deeply until secure.






(5) (6) Rear window (Figure 3) Body outside Product (4) Removed weather strip Restore

(5) Remove all of the (red) release paper for the double-sided tape on the stitching side of the product, and then temporarily secure the Wrangler (JL) and (JK) in place at the center of the ceramic line (yellow line) for both. (Figure 3) \* The installation surface varies depending on the model year of the vehicle. Refer to the images below.





The installation position on the rear window for later Wrangler (JK) models introduced from 2011 (without mesh) Attach to the end of the ceramic line.

(6) Temporarily fix the product in place at the center and install it along the yellow line, referring to step (5). (Figure 3)

